



# Application Note:

## Integrating Accuenergy RGM (Revenue Grade Meter) with Sol-Ark 3-Phase Hybrid Inverters

**Disclaimer:** It's important to carefully read and follow all local code, manufacturer's instructions, and safety guidelines. Sol-Ark LLC disclaims all liability for any personal injury, property damage, or other damage that may result from misapplying the information in this document.

### Overview

The Acuvim RGM metering solution, when properly configured, overrides the internally integrated metering of Sol-Ark's **30K-3P-208V** and **60K-3P-480V** Hybrid Inverters. Within a project installation, this metering solution:

- *Extends the metering measurement* beyond the CT distance limitation of the inverter's integrated metering.
- *Meets the revenue grade metering requirement* for applicable market incentives / utility metering agreements.

### Scope

This document covers selecting, installing, and programming the **Acuvim EL** and the **AcuPanel 9104X** RGM systems, as well as integrating them with Sol-Ark 30K-3P-208 and 60K-3P-480 Hybrid Inverters.

**IMPORTANT!** Refer to the Accuenergy meter manual for instructions relevant to the AcuPanel interconnections.



## Recommended Hardware

These Accuenergy RGMs have been tested with **Sol-Ark 30K-3P-208V** and **60K-3P-480V** inverters:

| Manufacturer      | Model          | Compatible CTs   | Communication Protocol | Voltage     |
|-------------------|----------------|------------------|------------------------|-------------|
| <b>Accuenergy</b> | Acuvim EL      | 333 mV CT        | Modbus RTU             | 208V / 480V |
|                   |                | Rogowski Coil CT |                        |             |
| <b>Accuenergy</b> | AcuPanel 9104X | 333 mV CT        | Modbus RTU             | 208V / 480V |
|                   |                | Rogowski Coil CT |                        |             |

### Notes

- The installer is responsible for choosing the correct CT sensor for the intended application.
- Rogowski coils are not recommended for zero export due to low accuracy in low power applications. PCS certification may be compromised with use of external meters.

## Required Firmware

The inverters must be on the following firmware:

- MCU version **1110**
- COMM version **104F**




## Connecting and Installing the RGM Systems

### Acuvim EL

**Note:** Please verify the manufacturer's installations recommendations.


#### RS 485 Communication Wiring

1. Use a Cat6 UTP communication wiring using a **T568B RJ45 standard**
2. Connect the RJ45 end to the inverter's **Meter** port
3. Connect the other end of the communication wire to the RGM's **COMM** terminal as shown in the diagram on the next page
4. Connect the **white-orange cable** to terminal **B**
5. Connect the **orange cable** to terminal **A**



# AcuPanel 9104X


3 Phase 3 Wire V<690V (line to line)



## Programming

### Sol-Ark Inverter Settings

1. Enable **Meter > Grid**.
2. Specify the **Meter Select** setting on **Accuenergy** (use Up and Down arrows to set the RGM).
3. Program the inverter to **Limited Power to Home** mode to collect readings from the Accuenergy RGM.



| Time  | Power(W) | Batt | Charge | Sell |
|-------|----------|------|--------|------|
| 01:00 | 30000    | 80%  |        |      |
| 05:00 | 30000    | 80%  |        |      |
| 09:00 | 30000    | 80%  |        |      |
| 13:00 | 30000    | 80%  |        |      |
| 17:00 | 30000    | 80%  |        |      |
| 21:00 | 30000    | 80%  |        |      |



## Program the Accuenergy RGM

On the **SYS settings** screen, specify these settings to communicate readings to the inverter:

| Setting                            | Required Value                                |
|------------------------------------|---|
| <b>S01: Modbus SN</b>              | 1   |
| <b>S02: Baud Rate</b>              | 19200   |
| <b>S04: Voltage Wiring Mode</b>    | 3LN   |
| <b>S05: Current Wiring Mode</b>    | 3CT   |
| <b>S08: Primary rating of CT</b>   | As established on the CT used                 |
| <b>S09: Secondary rating of CT</b> | 333 mV or 120 / 60 (when using Rogowski Coil) |
| <b>S033: Parity</b>                | NON1  |


## Verify RGM Functionality


To verify that the RGM is communicating properly, follow these steps.

1. Make sure the inverter does not have the **W04\_Meter\_Comm\_Fail** alarm active.
2. Verify the magnitude of the readings:
  - a. On the inverter screen, tap the battery icon --> **Detail volt view**
  - b. Check the values under **HM** to verify that they're populated correctly and correspond to the amount of power imported from or exported to the grid

| Load           |          | Grid                |          | Inverter           |          |
|----------------|----------|---------------------|----------|--------------------|----------|
| 313 W          |          | -19960 W<br>60.0 Hz |          | 20273 W<br>60.0 Hz |          |
| L1N:126V       | 125W     | L1N:124V            | 53.0A    | L1N: 124V          | 53.0A    |
| L2N:125V       | 71W      | L2N:123V            | 53.3A    | L2N: 124V          | 52.8A    |
| L3N:126V       | 117W     | L3N:124V            | 53.2A    | L3N: 124V          | 52.9A    |
| <b>Battery</b> |          | HM:                 | LD:      | INV_P:             |          |
| 20790W         |          | 4W                  | -6653W   | 6778W              |          |
| 20790W         | 0W       | 1W                  | -6652W   | 6723W              | AC_T:    |
| 98%            | 92%      | 1W                  | -6655W   | 6772W              | 52.6 C   |
| 418.1 V        | 0.0 V    | <b>PV</b>           |          |                    |          |
| 49.73 A        | 0.00 A   | PV:0.00kW           |          |                    |          |
| 30.0 C         | -100.0 C | M1:0.00kW/          | 0V/ 0.0A | M2:0.00kW/         | 0V/ 0.0A |
|                |          | M3:0.00kW/          | 0V/ 0.0A | M4:0.00kW/         | 0V/ 0.0A |

## Appendix







## Document Revision History

| Rev. | Date       | Author     | Description of Changes |
|------|------------|------------|------------------------|
| 1    | 04/14/2026 | Jose Rubio | Document Created       |
|      |            |            |                        |